

***** DRAFT – NOT FOR FILING *****

3745-512-350

Added geologic material layer, liner system, and leachate collection system tie-in area.

- (A) Added geologic material and engineered components in the liner system and leachate collection system tie-in area shall be inspected by the owner or operator, and if damage or deterioration is evident, tested prior to beginning construction of adjoining added geologic material and liner system and leachate collection system to confirm that none of the engineered components was damaged and that all engineered components continue to meet all specifications required to be certified as applicable to the engineered component.
- (B) If an engineered component in the tie-in area was damaged or does not meet all the specifications required to be certified, as applicable for the engineered component, the owner or operator shall comply with the procedures for failed tests and alterations in rule 3745-512-55 of the Administrative Code.